


NYU IFA LIBRARY



3 1162 04538834 6




THEODORE M. DAVIS'

EXCAVATIONS :

BIBÂN EL MOLÛK.

THE TOMB OF

IOUIYA AND TOUIYOU.



THE CHARIOT.

THEODORE M. DAVIS'

EXCAVATIONS: BIBÂN EL MOLÛK.

٢٠٠٧

THE TOMB OF

IOUIYA AND TOUIYOU.

THE FINDING OF THE TOMB,

BY

THEODORE M. DAVIS.

NOTES ON IOUIYA AND TOUIYOU,

BY

GASTON MASPERO.

DESCRIPTION OF THE OBJECTS FOUND IN THE TOMB,

BY

PERCY E. NEWBERRY.

ILLUSTRATIONS OF THE OBJECTS,

BY

HOWARD CARTER.

LONDON:

ARCHIBALD CONSTABLE AND CO., LTD.

1907.

NEW YORK UNIVERSITY
WASHINGTON SQUARE COLLEGE
LIBRARY

157-2-1	CT
BI	CI
AC WFE 195	LT
BD	RT

CONTENTS.

	PAGE
PREFACE ; BY THEODORE M. DAVIS.	VII
LIST OF PLATES AND ILLUSTRATIONS	IX
NOTICE ON IOUIYA AND TOUIYOU BY PROFESSOR GASTON MASPERO	XIII
THE FINDING OF THE TOMB BY THEODORE M. DAVIS	XXV
DESCRIPTION OF THE OBJECTS FOUND IN THE TOMB BY PERCY E. NEWBERRY :—	
THE SARCOPHAGUS OF IOUIYA	1
OUTER COFFIN OF IOUIYA	4
SECOND COFFIN OF IOUIYA	6
INNER COFFIN OF IOUIYA	9
MASK AND MUMMY-STRAPS OF IOUIYA	10
CANOPIC JAR-BOX OF IOUIYA	11
BOOK OF THE DEAD	13
THE SARCOPHAGUS OF TOUIYOU	16
OUTER COFFIN OF TOUIYOU	19
INNER COFFIN OF TOUIYOU	20
MASK AND MUMMY-STRAPS OF TOUIYOU	22
CANOPIC JAR-BOX OF TOUIYOU	23
FUNERARY STATUETTES OF IOUIYA AND TOUIYOU	26
ALABASTER VASE BEARING THE NAMES OF AMENOPHIS III AND QUEEN THYI	28
MAGICAL FIGURE OF IOUIYA	29
ALABASTER VASE	30
ALABASTER VASE	31
DUMMY VASES	32
AMULETS	33
THE CHARIOT	35
CHAIR OF PRINCESS SAT-AMEN	37
CHAIR BEARING THE NAMES OF QUEEN THYI AND PRINCESS SAT-AMEN	42
OSIRIS BEDS	45
COFFER BEARING THE NAMES OF AMENOPHIS III	46
COFFER BEARING THE NAMES OF AMENOPHIS III AND QUEEN THYI	47
STAFF AND WHIP	48

PREFACE.

I DESIRE to express my gratitude to Monsieur Maspero for writing the Notes on Iouiya and Touiyou.

THEODORE M. DAVIS.

NEWPORT,
RHODE ISLAND,
U.S.A.

LIST OF PLATES.

PLATE		
I.	THE CHARIOT	<i>Frontispiece</i>
II.	FULL-FACE AND PROFILE OF THE MUMMY OF IOUIYA	<i>facing page XII</i>
III.	PROFILE AND FULL-FACE OF THE MUMMY OF TUIYOU	„ „ XIV
IV.	THE ENTRANCE TO THE TOMB	„ „ XXIV
V.	POTTERY BOWLS FOUND ONE ON EITHER SIDE OF THE DOOR TO THE INNER CHAMBER	„ „ XXVI
VI.	SARCOPHAGUS OF IOUIYA	<i>following page 48</i>
VII.	OUTER COFFIN OF IOUIYA	„ „
VIII.	SECOND COFFIN OF IOUIYA	„ „
IX.	INNER COFFIN OF IOUIYA	„ „
X.	CANOPIC JAR-BOX OF IOUIYA	„ „
XI.	PAGE FROM PAPYRUS BOOK OF THE DEAD OF IOUIYA	„ „
XII.	SARCOPHAGUS OF TUIYOU	„ „
XIII.	OUTER COFFIN OF TUIYOU	„ „
XIV.	INNER COFFIN OF TUIYOU	„ „
XV.	CARTONNAGE MASK OF TUIYOU	„ „
XVI.	CANOPIC JAR-BOX OF TUIYOU	„ „
XVII.	CANOPIC JAR WITH MUMMIFIED LIVER SURMOUNTED BY CARTON- NAGE MASK	„ „
XVIII.	GOLD AND SILVER-PLATED SHAWABTI FIGURES OF TUIYOU	„ „
XIX.	WOODEN SHAWABTI FIGURE OF IOUIYA	„ „
XX.	WOODEN SHAWABTI FIGURE OF IOUIYA WITH BOX	„ „
XXI.	MODEL IMPLEMENTS OF SHAWABTI FIGURES	„ „
XXII.	MAGICAL FIGURE OF IOUIYA	„ „
XXIII.	MODEL COFFIN AND RECUMBENT FIGURE	„ „
XXIV.	ALABASTER VASE OF AMENOPHIS III AND QUEEN TIYI	„ „
XXV.	ALABASTER VASE	„ „
XXVI.	ALABASTER VASE	„ „

PLATE	
XXVII.	PAINTED DUMMY VASES OF WOOD <i>following page 48</i>
XXVIII.	PAINTED DUMMY VASES OF WOOD " "
XXIX.	PAINTED STONE VASES ON WOODEN STANDS " "
XXX.	MUMMIFIED JOINTS IN WOODEN CASES " "
XXXI.	MUMMIFIED BIRDS IN WOODEN CASES " "
XXXII.	BACK VIEW OF CHARIOT " "
XXXIII.	CHAIR OF SAT-AMEN " "
XXXIV.	BACK VIEW OF CHAIR OF SAT-AMEN " "
XXXV.	CHAIR WITH CUSHION " "
XXXVI.	CHAIR OF TIYI AND SAT-AMEN " "
XXXVII.	BED WITH PANELLED HEAD-PIECE " "
XXXVIII.	COFFER BEARING THE NAMES OF AMENOTIES III " "
XXXIX.	COFFER BEARING THE NAMES OF AMENOTIES III AND QUEEN TIYI " "
XL.	PAINTED WOODEN BOX OF AMENOTIES III " "
XLI.	PAINTED WOODEN BOXES OF IOUIYA " "
XLII.	WIG BASKET " "
XLIII.	OBJECTS FROM THE TOMB OF IOUIYA " "
XLIV.	PAPYRUS AND LEATHER SANDALS " "

LIST OF ILLUSTRATIONS IN THE TEXT.

	PAGE
PLAN AND SECTIONAL ELEVATION OF THE TOMB	XXIV
GILT STUCCO PANELS FROM BED AND CARVED CHAIR BACK	36
DECORATION ON BACK OF THE CHAIR OF PRINCESS SAT-AMEN	38
LEFT-HAND PANEL OF ARM OF CHAIR OF SAT-AMEN	39
RIGHT-HAND PANEL OF ARM OF CHAIR OF SAT-AMEN	40
DECORATION ON BACK OF THE CHAIR BEARING NAMES OF QUEEN TIYI AND SAT-AMEN	43

NOTICE ON IOUIYA AND TOUIYOU.



FULL FACE AND PROFILE OF THE MUMMY OF IOUIYA

NEW YORK UNIVERSITY
LIBRARY




NOTICE ON IOUIYA AND TOUIYOU,










BY












G. MASPERO.

STRICTLY speaking, these two individuals are not in themselves historical characters: it is through their daughter Tiyi, wife of Amenôthes III and mother of Khoumiationou, that they attract the attention of modern historians of Egypt.












§ I.—NAMES AND TITLES OF THE TWO PERSONAGES.









The name of the wife is spelt consistently with the exception of a few differences in calligraphy usual at this period. It is written , less frequently , , with or without the female determinative: the probable reading of it is *Touíyou*.

The man's name assumes several forms of spelling, which differ somewhat from each other: these are not all to be found on the same monument. It appears that each scribe or craftsman employed in the making of the funereal furniture had adopted his own rendering of the name for the objects that he decorated. On the black square sarcophagi and on the gilded coffins for the human remains the name is written , and exceptionally , with or without the determinative for the dead; but one meets  on the two small scent chests, and on the canopic boxes , on the small *ouashbaation* [ushabti] coffin , and rarely , , , and  on

the *ouashbaatiou* (ushabti) themselves ; finally  on the remains of the gilded cartonage, and  on the small limestone vases capped by figures of animals. All these varieties group themselves around two chief forms, both dissyllabic, both beginning with  or with its variants  and , once , but where the sounds  and  interchange. To judge from the number of the variants, the most usual pronunciation would be  *Iouia*, but it would be equally well pronounced  *Iaia* by interchange of the vowels, and even  *Iaia*. In names composed exclusively of vowels or semi-vowels, pronunciation has always a tendency to fluctuate more easily than in names that are full of consonants.







Of their titles, some denote real functions, others are those of courtesy. Collecting them together from the monuments throughout which they are scattered, the following groups are obtained :—














Firstly for the man,  or  or ;  developed into , , , , ; ; , with its variants  and , once ; ; ; ; ; ; ; ; ; ; .











The above are the real titles of the dead. The first indicate his rank at court . *Rapâiti-hâiti* classes him among the feudal nobility, whilst  *Niti? baïti* and  *Samirou* would accord to him in the ranks of the priesthood the position of “one attached to the Person of the king” (*Homme au collier du roi*) of Lower Egypt, and “friend”; the title of “friend” in the titulary of Upper Egypt appears to correspond with the title “one attached to the Person” in the titulary of Lower Egypt. The accompanying symbols which qualify the word  prove that he held an eminent place among the people of this class: he was in truth “the first friend of the friends”  *samir tapou ne samirou*, and “first friend of those who love the king of Upper Egypt and of those who love the king of Lower Egypt”  *samir-tapou marourou souton, marourou baïti*, and then “unique friend of love”  *samir uâou-ni-marouît*, or  *samir âou-ni-marouît*. The second class of titles














PROFILE AND FULL-FACE OF THE MUMMY OF TOUIYOU


denote the active duties he fulfilled, and they show us that his services were of the priestly order. Two of them are only suggested in passing, and as if with reluctance, those of “the prophet of Minou”  *honnoutir ni Minou*, and “the superintendent of the (sacred) oxen of Minou, the lord of Akhmim”  *nas-ahaou ni Minou nab Iapou*. His title of “master of the horse, lieutenant of the king for the chariots,” comes only once, and seems to prove that he had been connected with the war-administration, not that he ever went to the wars. The one title to which he holds and which describes him is that of  *iat-noutir*, or “divine father,” of which the usual variants are  *iatf-noutir* and . One of these variants,  *iatf-noutir ni nab taoui*, “the divine father of the gods of the two lands” (that is to say, the king), is important, as we shall have occasion to see.

After the titles proper come titles by courtesy, which are numerous. Iouiya is called  *ouaou akiron*, “the one wise,” and  *súaou ni sounton saoukiron ni baíti iri ni nab-taou-ka-f*, which, translated, verbally means “he who is *le fait grand* of the king of Upper Egypt, *le fait sage* of the king of Lower Egypt,” in French, “celui que le roi a rendu grand et sage” [he whom the king has made great and wise], “for whom the king has made his double.” One variant gives  *súaou ni nab-iri-khaítou*, with the title of  “lord [or master] to do what pleases him” which belongs to the king. The most noteworthy series of these epithets includes the words  *Hosou* and  *marout*:  *hosoui paroui me khaítou hosouiou*, literally, “he whose praises are sung, coming out from the mass (lit., “from the body”) of those whose praises are sung,” or nearly, “the favourite excellent above all favourites,”  *hosoui ni noutir nofir*, “the favourite of the good god,”  *hosoui ni nab-taoui*, “the favourite of the lord of the two lands,”  *hosoui ni nabou-f*, “the favourite of his lord,”  *hosoui ni Horou mepaou-f*, “the favourite of the Horus in his palace.” Most commonly the designation “lord” indicates the king, but in other cases it denotes a god,  *hosoui ni nabou-f Amanou*, “the favourite of his lord Ammon,”  *Nab hosouítou khar nab-taoui*, “the

lord of favours under the lord of the two lands,"  *didou-hosouïtou man marouït khar nabou-f Osiri*, literally, "the lasting of favours, the unchanging of love under his lord Osiris,"  *man marouït khar nabou-f ashaou hosouïtou me par-soutou*, that is to say, "he who rejoices in the unchanging love of his lord, and who has many favours in the Royal Palace"; in short, he is the  *mah-iabou ni noutir noufir*, "he who fills the heart of the good god" and  *marouï nabou-f*, "he who loves his lord,"  *mah-iabou ni soutou me ta-re-zarou-f*, "he who fills the heart of the king in the whole land," with other ordinary expressions which are used in reference to all people of high rank,  *ouâou iabou ni soutou ane mah-snaou-f*, "the unique beloved of the king, without a second,"  *âm-iabou ni noutir noufir*, "he who is in the heart of the good god,"  *ra-ni-soutou ânkhoui-nou-baïti*, "the mouth of the southern king, the two ears of the northern king," and so on. The whole extent of his favour is summed up in the expressive sentence:  *rapûiti haïti nasou tenou ounouït re shapou hosouïtou nabou-taoui*, "the prince who is called at any hour to receive the praises (lit. 'the songs') of the lord of both lands." His coffin was  *ironi me hosouïtou nit khir soutou*, "made by the special favour of the king."

For the wife the titles and formulæ are less varied than for the man. It is apparent that in the beginning her real duties were at court in her capacity of  *khakerouït souten*, "dresser to the king," and at the temple of  *qamaït ni Amanou*, "chantress of Amon," and of  *ouarït khonai nit Amanou*, with the variant  *ouarït khonait ni Amanou*, "lady of the harem of Amon"; just as her husband was attached to the cult of Minou of Panopolis, as we have already seen above, she held in relation to that god the same position as she held to Amon,  *ouarït khonait ni Minou*, "lady of the harem of Minou." Her customary attribute in her capacity of "dresser to the king" is  *hosouït nit noutir noufir*, "favourite of the good god," with the purely grammatical variants  *hosoui nit noutir noufir*, and of  *hosouït nit noutir noufir*.




hosouit ni noutir nofir. Sometimes, however, she is called  *hosouit ni Hathor*, “the favoured of Hathor.” Always her principal title, that of which she was most proud, and which brought her chiefly before the notice of her contemporaries, is that of , variant  *maout soutou ni himît soutou ouarît*, “royal mother of the chief-wife of the king.” This is repeated jealously on the coffins, on the furniture, on the *ouashbaatiou* [ushabti figures], in such a manner that the day an intruder should penetrate into the tomb, he would know from what to refrain on account of the quality of one of the persons resting there, and would not be able to plead the excuse of ignorance if he persisted in his intention of despoiling the mummy.

To sum up, Iouiya and Touïyou possessed a double set of titles, corresponding to the two successive conditions of their career. At their outset they are people of mediocre position. The one, Iouiya, is “divine father,” that is to say, if the title is a priestly title, he occupied one of the least important positions in the priestly order, one which was bestowed upon children; the other, Touïyou, fills a position which brings her into relations with the sovereign, that of “dresser” [mistress of the robes] , and she is, like all the ladies who attended the court, “chantress of Amon.” Perhaps the titles that belong to them in the priesthood and administration of the god Mînou of Panopolis show to us that the two conjointly, or at least the more important of the two, namely, Iouiya, originally came from Akhmîm.

There is, perhaps, reason to think that the post occupied at court by Touïyou facilitated the marriage of her daughter with the sovereign. The daughter came to the palace, where she would reside with her mother, supposing the latter to have had apartments therein, as it is possible, considering her position; it is there that Amenôthes III, or, if the marriage was arranged by the regent-mother of Amenôthes III, that the former was able to see the young girl. It has happened more than once in Oriental harems that a woman of no particular position, or a simple slave, devoted to the amusement of a young prince whilst waiting the opportunity for a suitable marriage, has gained so great a hold upon her young master that she has got herself espoused and become queen. What we now know of the parents of Tiyi and of their circumstances, allows us to conjecture some such adventure. The Pharaoh, in making their daughter his wife, loaded them with favours, and heaped on them the second mass of titles of which I have spoken: there it was that Iouiya became *divine father of the lord of both lands*, if

the title must really, as Borchardt has given very good reasons to believe, be interpreted in such cases *father-in-law of the king*.¹ For the rest, we do not see that they played any part in State affairs: they remained the private parents of a queen, and were never otherwise.

§ II.—THE CHILDREN.

Touiyon had two children, or at least we know the names of two of her children, the only ones perhaps who lived to grow up: a son whose existence has been proved to us by the legends on her sarcophagus and on her coffin,  *Sai-s honnoutir mah-snaou ui Amanou hosouï ui noutir nofir Aauenou*, “the second prophet of Amon, the favourite of the good god Aamenou.” The daughter became the Queen Tiyi , the favourite of Amenôthes III and the mother of Amenôthes IV Khoumiationou. None of the inscriptions found in the tomb say that Tiyi was the daughter of Iouïya, and one would be able to suppose that she was born of a previous marriage of Touiyon, if the legends on the large scarabs of Amenôthes III did not definitely state that she had as father Iouïya .

For the last half-century many efforts have been made to prove that Queen Tiyi was not of Egyptian extraction, but Asiatic, in consequence of her father and mother being Syrians, whether private individuals or princes. Without dwelling upon more remote work, I will quote what has been written upon this subject by Petrie and Budge in their histories of Egypt. Petrie comes to the conclusion from the facial type of Tiyi upon the monuments and the resemblance which she bears to one of the Asiatic prisoners at Karnak, “that she belonged to Northern Syria.” He declares that the name of her parents may equally well be Egyptian as foreign, but from the character of the titles which she bears, he concludes she was an hereditary princess of blood royal. “She could have easily been grand-daughter of an Egyptian king and queen, her mother Thuaa having been married to some North Syrian prince Yuua. Thus she would have the

¹ L. Borchardt, *der ägyptische Titel “Vater des Gottes” als Bezeichnung für “Vater oder Schwiegervater des Königs,”* extract from the *Berichte der K. Sächsischen Gesellschaft der Wissenschaften zu Leipzig*, LVII, pp. 256–270.

“right to be a ‘princess of both lands;’ her name might be Egyptian; and “she would rightfully fill the prominent place she did in Egypt; while her “physiognomy would be Syrian. This view cannot be yet proved, but it “certainly fulfils all the conditions closely.”¹

Budge, on his side, assures us that “of all the Mesopotamian or North “Syrian women whom Amen-hetep married, the best beloved was the “beautiful Thi, or Tii None of the other Asiatic wives was “acknowledged to be ‘Queen of Egypt,’ this honour being reserved solely “for the lady Thi : she seems not to have belonged to any royal “house in Mesopotamia, but it is perfectly certain that she was accorded the “highest rank and honour which a woman could obtain in Egypt, when she “is described as ‘royal daughter, royal sister, royal mother, royal wife, great “lady, lady of the South and North.’ The lady with whom she is identified “is represented as having a fair complexion and blue eyes, and she has all “the physical characteristics of the women belonging to certain families who “may be seen in North-Eastern Syria to this day.”²

It is interesting to look into the reasons that moved the Egyptologists of the last generation to believe and attempt to prove that queen Tiyi was a foreigner. Some are of moral sort, others material. Struck, in fact, by the influence she exercised over her son Amenôthes IV, and by the part which she seemed to take in the ritual of the cult of Atonou, they questioned if it was not owing to her that this cult came into such sudden favour. Just as Atonou has the ring of the names of the Semitic divinities Adonaï, Adonis, they concluded that Atonou was a Semitic god, in consequence of the queen being a Semite, or at least of Syrian extraction. In searching for proofs of the above hypothesis, they found them clad in a shroud of facts, or rather conjectures, which they arranged for themselves skilfully. There was in the “Bab el-Harim” the tomb of a queen whose name Δ_{ω}° Taïti, transcribed into modern languages, presented a remote similarity with that of 𓆎𓆏𓆑𓆒𓆓 Tiyi: these they identified with each other, and all that is attributed to the second they attributed to the first. Again, in 1893, Mr. Budge showed that “the “tomb of a queen Thi, who is designated royal daughter, royal sister, royal “wife, chief lady, regent of the North and South,³ was opened at the beginning “of this century at Thebes. It would hardly be possible to doubt that this

¹ Petrie, *A History of Egypt*, 3rd edit., Vol. II, pp. 182, 183.

² Budge, *A History of Egypt*, Vol. IV, pp. 96–98.

³ Brugsch, *Recueil de Monuments Égyptiens*, Vol. II, Pl. LXIII, i.

“ was the tomb of the principal wife of Amenophis III. The portrait of this “ lady ¹ represents her with a fair complexion and blue eyes; the colour of “ the skin is that of the complexion of the original people of the north-east of “ Syria. Thi was the mother of Amenophis IV. She also gave birth to a “ daughter Set-Amen.² The British Museum possesses a kohl pot of blue “ faïence³ and a double case for kohl in wood⁴ with the name of Amenophis “ and of Thi. They formed, probably, part of the toilet requisites deposited “ in the tomb for the use of the queen.”⁵ The identification was a mistake, and the queen buried at Bab el-Harim had nothing in common with Tiyi, not even the name; she was called Taïti Δ_{11}° , as I have said before, and she lived during the XXth dynasty, as is proved by the character of her tomb.

The points brought forward to give proof of her Asiatic origin do not exist, or prove nothing. She has not blue eyes, as is ordinarily stated: the drawing by Rosellini, to which one refers for detail, gives her dark eyes, and the blue eyes which one sees in *l'Histoire de l'Art Égyptien* are a restoration by Prisse d'Avennes, which nothing that is to be seen on the monuments justifies. As to the white, or rather pink, hue with which the skin of Taïti is coloured, I have already had occasion to point out by numerous examples that this was the fashion at many times during the Theban period: the men and women painted themselves in this manner to lighten the colour of their skin, and it would be wrong to see a suggestion of origin in what was merely a caprice of fashion. The identification of Taïti with Tiyi cannot be upheld a moment when the original documents have been resorted to; but the mistake by which this had been produced, and the false conclusions drawn from it, once it was scattered through the world of scholars and intelligent readers, could no more be destroyed. Assiriologists in particular are attached to this theory with still greater persistency perhaps than Egyptologists, and it is they above all who have insisted that Tiyi was daughter and sister of the kings of Mitanni. The chief reason they bring forward is that these princes call her “ their sister;” but the terms “ brother ” and “ sister ” already formed part of the international courtesies at this distant epoch, and no more than now in such a case would

¹ Rosellini, *Monumenti Storici*, Pl. XIX, No. 22.

² This is proved by an inscription engraved on a piece of wood in the British Museum, No. 5899a.

³ No. 2572b, Fourth Egyptian Hall, North Gallery, Case E.

⁴ No. 2598a, Fourth Egyptian Hall, Case E.

⁵ Bezold-Budge, *The Tell el-Amarna Tablets in the British Museum*, pp. xix, xx.



it imply family relationship. Everything considered, the hypothesis of Syrian origin for Queen Tiyi rests upon a collection of mistaken theories and of badly interpreted facts; and as she herself was the only valid reason for making Iouïya and Touïyou foreigners, the desire to make them other than Egyptian must be renounced at once. Equally their titles connect them with Egyptian sacred rites. Their names have not the form of Mitanni names as Doushratta, Tadoukhipa, Giloukhipa, but they resemble Libyan names so frequent in Egypt.

The racial type of the woman is like enough that of the queen Tiyi according to the statues, and it is certain that she very closely resembled her mother; notwithstanding that, she possesses some of the firmness noticeable in her father. As to deciding from these particulars whether her parents were of African or Asiatic race, I will not hazard an opinion; nothing is less certain than ethnographical conclusions drawn from the examination of bas-reliefs when it is not concerned with races as different in type as black from white. A people like that of the Egyptians contained in themselves every variety of type possible, whether these types spring naturally and without mixing from the original type, whether they result from alliances more or less remote with individuals belonging to a foreign unmixed race, or to the Egyptian race contaminated more or less by foreign elements. The profile of the queen Tiyi recalls to Mr. Petrie that of a Syrian prisoner. The head of a statuette of this same queen discovered at Sinai during the winter of 1905, recalls to me the impression of women of the Ababdehs and Begas whom I have seen at Assuan: I could thus assign to Iouïya a Nubian origin. When criticism is so undecided, the best is to abstain and to reserve judgment. Until we have new evidence, I shall consider that Iouïya, Touïyou, and Tiyi as being natives of the country wherein they lived and where their mummies have been found.

§ III.—THEIR AGE.

Iouïya and Touïyou died at a fairly advanced age: their hairs are white, and the examination of their bodies does not contradict the verdict of their hair. It will not be a mistake to state that they had reached an age over sixty. From the relative position of the two sarcophagi in the tomb, it seems that the husband was the first to die; but the material is lacking to decide this question.

THE FINDING OF THE TOMB OF IOUIYA
AND TOUIYOU.



PLAN AND SECTIONAL ELEVATION OF THE TOMB.



CLIFFS NEAR THE TOWN

THE FINDING OF THE TOMB OF IOUIYA AND TOUIYOU.

In the "Valley of the Kings," on the west side of the Nile at Thebes, there is a narrow lateral valley, nearly half a mile long, leading up to the mountain. At the mouth of this valley there is a foothill about sixty feet high, in the side of which Ramses III commenced a tomb, and beyond which Ramses XII excavated his tomb. In the winters of 1902 and 1903 I undertook to clear and explore this valley, commencing just above the tomb of Ramses XII, and continuing my work until I reached the mountain. It resulted in the discovery of the tombs of Thoutmôsis IV and of Queen Hâtshopsîtû.

On the 20th of December, 1904, I resumed my explorations in the lower end of the lateral valley, which I was enabled to do owing to the kindness of Mr. J. E. Quibell, the Chief Inspector at Thebes, who, with the approval of Monsieur Maspero, Director-General of the Cairo Museum, undertook the employment and superintendence of my workmen, pending my arrival in the valley.

On my arrival in January, 1905, I found that the work on the location selected had yielded nothing and gave no promise. Consequently I abandoned the site, and transferred my workmen to the unexplored space between the tombs of Ramses III and Ramses XII, heretofore described.

The site was most unpromising, lying as it did between the Ramses tombs, which had required many men for many years; therefore it did not seem possible that a tomb could have existed in so narrow a space without being discovered. As an original proposition I would not have explored it, and certainly no Egyptologist, exploring with another person's money, would have thought of risking the time and expense. But I knew every yard of the lateral valley, except the space described, and I decided that good exploration justified its investigation, and that it would be a satisfaction to know the entire valley, even if it yielded nothing.

From the 25th of January, 1905, until the 5th of February, the work progressed without sign of promise. My daily visits were most discouraging, but on my arrival at the work on the 6th February, I was greeted by my Reis (Captain) and workmen with great acclamation. I quickly made my way to the spot, where I saw a few inches of the top of a well-cut stone step, which promised steps below and the possible existence of a tomb.

From the 6th of February until the 11th my workmen were hard at work removing the overhanging *débris* which concealed the door; but before the night of the 11th a small portion of the doorway was exposed, and from that moment the opening was guarded day and night by policemen and valley guards. At the close of the twelfth day the door was entirely cleared—a most satisfactory sight! It was cut in the solid rock, and was 4.02 metres high and 1.35 wide, with a decorated lintel. The doorway was closed within eighteen inches of the top with flat stones, about twelve inches by four, laid in Nile mud plaster. This opening clearly indicated that, at some early date, the tomb had been entered and probably robbed—a most unwelcome indication! Although it was nearly dark, I concluded to have a look through the opening. Mr. Arthur Weigall, the appointed but not formally confirmed Chief Inspector in succession to Mr. Quibell, had ridden out to the valley with me, and was invited to join me in the first sight of the corridor of the tomb. The opening was chin high, but we could dimly see a few yards of the corridor, which seemed to be about five feet wide and high, with a steep decline. As soon as my eyes became used to the semi-darkness, I saw what I thought to be a cane, or small club, lying on the floor a few feet from the doorway. Neither of us could get up to the opening, nor through it, without a ladder—which did not exist in the valley—so I selected a small native boy and had him lifted up to the opening, through which he entered. We watched the boy closely and saw him pick up the cane; then he came towards us, picked up two other objects and passed them to me. They proved to be a wooden staff of office, a neck yoke, and a large stone scarab, covered more or less with gold-foil, which made it seem, at first glance, to be solid gold.

Happily, Monsieur Maspero was on his dahabeah at Luxor, and, as soon as I reached mine, I wrote him a note asking him to come over and see something worth looking at. Shortly thereafter he came, followed by Professor Sayce, and we not only enjoyed the discoveries of the day, but were even more interested in the ownership of the tomb, as to which we had not the slightest clue. Monsieur Maspero requested me to open and enter



POTTERY BOWLS FOUND ON EITHER SIDE OF THE DOOR TO THE INNER CHAMBER

the tomb next day, that he might show it to H.R.H. the Duke of Connaught and party, who were expected to arrive on the following afternoon.

Consequently, next morning, Monsieur Maspero and Mr. Weigall joined me at the tomb, and I at once set the men to work taking down the wall which barred the outer door. It was very slow work, as every stone had to be examined for hieroglyphs and signs, and every basket of sand and *débris* sifted and examined for objects of interest which might be concealed in the deposit. However, nothing was found, and, in the course of an hour or so, the doorway was cleared.

The electric wire had been installed at the outer doorway, but as the introduction down the corridor would have required the services of electricians, we concluded that it would be safer to use candles for our entry and examinations. Monsieur Maspero and I and, at my invitation, Mr. Weigall, each with a candle, started down the corridor, which proved to be 1.75 metres wide and 2.05 metres high, cut out of the solid rock and descending so sharply as to require care not to fall. It was neither painted nor inscribed. After descending about twenty feet, we found a shelf cut into one side of the wall and on it a large ceremonial wig made of flax and dyed black, also an armful of dried flowers which doubtless were offerings to the dead (as is done in our day and generation). Passing on some 9 metres, we came to another flight of stone steps descending almost perpendicularly, at the bottom of which we found a doorway 2.10 metres high and 1.20 metres wide, closed with stones set in Nile mud plaster, with an opening at the top of about the same size as was found in the first doorway, confirming our fears of a robbery. The face of the wall was plastered with mud and stamped from top to bottom with seals.

On either side of this doorway, carefully placed to escape injury, stood a reddish pottery bowl about twelve inches wide, showing the finger-marks of the man who with his hands gathered the mud and plastered it on the doorway wall. In each bowl was a wide wooden stick, evidently used to scrape the mud from his hands. Having copied the seals, we investigated the possibility of entry without taking down the wall. We found that the opening which the robber had made was too high and too small to allow of Monsieur Maspero getting through without injury. Though we had nothing but our bare hands, we managed to take down the upper layer of stones, and then Monsieur Maspero and I put our heads and candles into the chamber, which enabled us to get a glimpse of shining gold covering some kind of furniture, though we could not identify it. This stimulated us to

make the entry without further enlarging the opening. I managed to get over the wall and found myself in the sepulchral chamber. With considerable difficulty we helped Monsieur Maspero safely to scale the obstruction, and then Mr. Weigall made his entry. The chamber was as dark as dark could be and extremely hot. Our first quest was the name of the owner of the tomb, as to which we had not the slightest knowledge or suspicion. We held up our candles, but they gave so little light and so dazzled our eyes that we could see nothing except the glitter of gold. In a moment or two, however, I made out a very large wooden coffin, known as a funeral sled, which was used to contain all the coffins of the dead person and his mummy and to convey them to his tomb. It was about six feet high and eight feet long, made of wood covered with bitumen, which was as bright as the day it was put on. Around the upper part of the coffin was a stripe of gold-foil, about six inches wide, covered with hieroglyphs. On calling Monsieur Maspero's attention to it, he immediately handed me his candle, which, together with my own, I held before my eyes, close to the inscriptions so that he could read them. In an instant he said, "Iouiya." Naturally excited by the announcement, and blinded by the glare of the candles, I involuntarily advanced them very near the coffin: whereupon Monsieur Maspero cried out, "Be careful!" and pulled my hands back. In a moment we realized that, had my candles touched the bitumen, which I came dangerously near doing, the coffin would have been in a blaze. As the entire contents of the tomb were inflammable, and directly opposite the coffin was a corridor leading to the open air and making a draught, we undoubtedly should have lost our lives, as the only escape was by the corridor, which would have necessitated climbing over the stone wall barring the doorway. This would have retarded our exit for at least ten minutes.

As soon as we realised the danger we had escaped, we made our way out of the chamber and, seating ourselves in the corridor, sent for workmen, who took down the door blocking the doorway. Then the electricians brought down the wires with bulbs attached, and we made our second entry into the chamber, each of us furnished with electric lights which we held over our heads, and we saw that every foot of the chamber was filled with objects brilliant with gold. In a corner stood a chariot, the pole of which had been broken by the weight of a coffin lid that the robber had evidently deposited upon it. Within a foot or two of the chariot stood two alabaster vases of great beauty and in perfect condition.

From the neck of one of the vases hung shreds of mummy-cloth which had originally covered the mouth of the vase. Evidently the robber, expecting the contents to be valuable, tore off the cloth. Three thousand years thereafter I looked into the vase with like expectation ; both of us were disappointed, for it contained only a liquid which was first thought to be honey, but which subsequently proved to be natron.

The mummies of Iouiya and Touiyou were lying in their coffins. Originally each mummy was enclosed in three coffins ; the inner one holding the body. Evidently the robber had taken the inner coffins out and then had taken off their lids, though he did not take the bodies out of their coffins, but contented himself with stripping off the mummy-cloth in which they were wrapped. The stripping was done by scratching off the cloth with his nails, seeking only the gold ornaments or jewels. At least that seems to have been the manner of robbing the bodies, as we found in both coffins, on either side of the bodies, great quantities of mummy-cloth torn into small bits. Among the shreds were found numerous valuable religious symbols, several scarabs, and various objects of interest and beauty. In lifting the body of Iouiya from his coffin, we found a necklace of large beads made of gold and of lapis lazuli, strung on a strong thread, which the robber had evidently broken when scratching off the mummy-cloth, causing the beads to fall behind the mummy's neck.

The robber had also overlooked a gold plate about the size of the palm of a man's hand, which had been inserted by the embalmer to conceal the incision he had made in extracting the dead man's heart for special mummification.

When I first saw the mummy of Touiyou she was lying in her coffin, covered from her chin to her feet with very fine mummy-cloth arranged with care. Why this was done no one can positively state, but I am disposed to think that the robber was impressed by the dignity of the dead woman whose body he had desecrated. I had occasion to sit by her in the tomb for nearly an hour, and having nothing else to do or see, I studied her face and indulged in speculations germane to the situation, until her dignity and character so impressed me that I almost found it necessary to apologize for my presence.

From all the evidence furnished by the acts of the robber, it seems reasonable to conclude that the entry into the tomb was made within the lifetime of some person who had exact knowledge of its location. Evidently the robber had tunelled through the overlying *débris* which concealed the door

of the tomb; otherwise he would have been compelled to remove a mass of rock and soil which would have required many days, and would also have exposed the robbery to the first passer-by. When the robber found the outer doorway barred by a wall, he took off enough of it to enable him to crawl through; and when he reached the second and last doorway, he found a corresponding wall, which he treated in the same manner. He seems to have had either a very dim light or none at all, for when he was in the burial chamber he selected a large stone scarab, the neck-yoke of the chariot, and a wooden staff of office, all of which were covered with thick gold foil, which evidently he thought to be solid gold: he carried them up the corridor until he came to a gleam of daylight, when he discovered his error and left them on the floor of the corridor, where I found them.

When the robber got out of the tomb, he carefully concealed the doorway and his tunnel with stones and *débris*, and did it so effectively, that it was not disturbed until its discovery three thousand years later.

The tomb which I have attempted to describe is the only one ever found which has contained in perfect condition the original deposit. It is sad to realize that thousands of kindred objects, probably more beautiful and instructive than the present find, have existed in tombs which in past years were robbed and their precious contents destroyed or scattered over the face of the world.

Though, under the letter of my permission to explore in the "Valley of the Kings," I was not entitled to any portion of the "find," Monsieur Maspero, with a generosity common to him, offered me a share. I confess that it was a most attractive offer, but, on consideration, I could not bring myself to break up the collection which I felt ought to be exhibited intact in the Cairo Museum, where it could be seen and studied by probably the greatest number of appreciative visitors.

THEODORE M. DAVIS.

DESCRIPTIONS OF THE OBJECTS

FOUND IN THE

TOMB OF IOUIYA AND TOUIYOU.

THE SARCOPHAGUS OF IOUIYA.

THE mummy of Iouiya was enclosed in three separate coffins, nested one within the other. These again were placed in a large rectangular wooden sarcophagus, the latter being mounted on a sledge with roller in front.

The sledge and sarcophagus are both of a coarse-grained wood covered with pitch and decorated with figures and hieroglyphic legends in stucco-gilt. In shape the sarcophagus is rectangular with a projecting curved cornice around the top; its lid is rounded on either side of a flat beam running down the axis, and has massive uprights at each end. The joints are mortice- and tenon-pinned and the roller is dovetailed into the frame of the sledge.

Down the central beam of the lid is a band of gold-foil with a hieroglyphic inscription in slight relief:—







On either side of this central band of hieroglyphs are four vertical lines of inscription which are continued down the sides of the sarcophagus: these inscriptions give prayers to the gods of the West for the deceased and recount Iouiya's various titles. Between these vertical lines of hieroglyphs, on both sides of the box, is a procession of gods: Thoth, Anset, Hapꜣ, and Anubis. At the top end of the right-hand side is figured a pylon with the double eyes above it. The inscriptions read:—

On the right-hand side:—

- (1) (2)

- (3) 
- (4) 

On the left-hand side :—


- (1) 
- (2) 
- (3) 
- (4) 

On the two ends of the lid are, in low relief, figures of Anubis seated on pylons facing one another.


Immediately beneath the beading which separates the cornice from the rest of the box and running right round it is a band of gold with hieroglyphic inscriptions in slight relief. On the two ends are figures of Isis and Nephthys (in gold-foil) standing on *nub*-signs and reciting the incantations for the protection of the dead which are given in the inscriptions above them.

These inscriptions read :—

On the head of the box, above the figure of Isis :—

- 

On the end, above the figure of Nephthys :—

- 

On the right side of the box is a prayer to Umnefer for the benefit of the *ka* of Iouiya :



On the left side of the box is a prayer to Osiris Khent-Amenti for the benefit of the *ka* of Iouiya :—



OUTER COFFIN OF IOUIYA.

THE outer coffin is mummyiform in shape, and, like the sarcophagus, is covered with pitch and ornamented with inscriptions and designs in stucco-gilt. The face and hands are gilt; the wig is long and the hair is represented by stripes of alternate black and gold. The eyes and eyebrows are inlaid: the eyebrows and lashes are of dark blue glass, the iris is of black obsidian and the white of white marble. Around the neck and upper part of the chest is a broad necklace in gold, and on the wrists are bracelets. Upon the abdomen is a vulture with outspread wings and holding the Q-rings in its talons. Down the front of the mummy case is a vertical line of hieroglyphs giving the title and name of Iouiya and the usual prayer to Nut:—



On either side of this central band of hieroglyphs are four vertical columns representing the mummy straps and inscribed with the titles and name of Iouiya. Between these vertical columns of hieroglyphs on both sides of the box is a procession of gods of the West, those on the right side being Mestha, Anubis, Duamutef and Geb: while on the left side are Hapÿ, Anubis, Qebhsenuf, and Nut. The inscriptions read:—

On the right:—

- (1) Iouiya.
- (2) Iouiya.
- (3) Iouiya.
- (4) Iouiya.

On the left :—

- (1) Iouiya.
- (2) Iouiya.
- (3) Iouiya.
- (4) Iouiya.




At the top end of the box on the right-hand side is figured a pylon with the double eyes above it, while on the left-hand side are two vertical lines of inscription stating that the coffin was made by favour of the king for Iouiya :—



- (1) (2)




Running round the head, sides and feet of the lid of the coffin is a band of gold-foil with four inscriptions. On the head of the box is a figure of Nephthys kneeling upon a *nub*-sign, and on the feet a figure of Isis also kneeling upon a *nub*-sign. The inscriptions round the lid give incantations for the protection of the dead, and read :—




- (1) Round the head :
- (2) On the feet :
- (3) On the right side of the body :
- (4) On the left side of the body :







The bands running round the front and sides of the case name the gods of the West, and give the following titles of Iouiya :—







On the right side of the coffin, on the box, is figured a procession of gods led by Thoth, with vertical lines of hieroglyphs between each figure. Before Thoth are two lines reading : (1)  (2)  Iouiya.





Then follow in order, Mestha : (1)  Iouiya (2)  (3)  

Anubis : (1)  (2)   Iouiya.

Duamut-ef : (1)  (2)   Iouiya  (3)  




Thoth : (1)  (2)   Iouiya.

On the left side of the coffin, on the box, is figured another procession of gods led by Thoth, and before him are the sacred eyes on a pylon and four vertical lines of hieroglyphs: (1)  (2) 
 (3)  (4) 

Then follow in order, Hapy, with three vertical lines of inscription before him: (1)  (2) 
 (3) 

Anubis: (1)  (2) 
 (3) 

Kebhsenuf: (1)  (2) *sic* 
 (3) 


Thoth: (1)  (2) 


Round the bottom of the lid runs a band from head to foot upon which are three inscriptions inscribed horizontally: these are the same as those round the head and sides of the outer coffin with only unimportant variants.

On the lid at the feet is a figure of Isis with arms upraised and kneeling upon a *nub*-sign. Below her on the box are represented a *ded* and two *sa* amulets each inscribed with its chapter from the *Book of the Dead* (Chapters CLV and CLVI).

INNER COFFIN OF IOUIYA.

LIKE the second coffin of Iouiya, the third or inner one is mummiform in shape; it is carved in wood, coated with stucco and gilt, and richly inlaid with semi-precious stones and coloured glass. The wig is long; the face and ears are exquisitely modelled; the eyebrows and lashes are of blue glass inlaid, and the eyes are of white marble and black obsidian. The necklace or pectoral is of gold inlaid with coloured glasses: its ends are the usual hawk-heads, and it is composed of rows of beads and pendants in the form of poppy and lotus petals inlaid in red, and light and dark blue glass.

Over the abdomen is a vulture in gold inlaid with coloured glasses, with wings outspread, and holding in its talons \ominus -seals of carnelian. Below it, covering the lower part of the abdomen and legs as far as the shins, is a standing figure of the goddess Nut in low relief, with arms upraised, and clad in a long close-fitting garment covered with bead work. She wears a long wig secured by a fillet over the forehead, a broad necklace, as well as bracelets and anklets. She stands upon a *nub*-sign.

On either side of the figure of Nut are vertical columns of hieroglyphs inlaid in coloured glasses. That on the right side gives the usual *de hetep seten* formula to Osiris Within the West, that he may give *per kheru* offerings for the benefit of the *ka* of Iouiya. On the left side the inscription gives the speech of Iouiya to Nut that she may spread her protecting wings over his body.





On the sides of the body are given in low relief the same inscriptions as are found on the second coffin, with figures of the Ibis-headed god Thoth at each end, and the gods of the West in the divisions between.

At the foot of the coffin is represented a figure of the goddess Isis kneeling upon a *nub*-sign. It is doubtful whether this case was originally made for Iouiya: another name seems to have been given on the sides, and that of Iouiya inserted over it.



MASK AND MUMMY-STRAPS OF IOUIYA.

MASK of Iouiya for fitting over the head of his mummy. It is made of several layers of coarse linen, glued together and coated with plaster. The inside is bitumened, the exterior is gilt. The wig is long, lined, and with bands at the ends. The face is finely modelled. The eyes, eyebrows and eyelashes are inlaid: the eyes are of white marble and obsidian, the eyelashes and brows are of blue glass. The pectoral consists of eleven bands of ornamental rectangles incised, with a row of drop-beads incised below. The chin and right side of the head are broken.

Fixed over the mummy wrappings of Iouiya were mummy-straps firmly secured by string behind. These are cut out of a piece of linen which forms their frame-work, and this is covered with stucco and gilt, with the margin painted green.

At the top is a figure of Nut with wings outspread, and on either side of her the amulets  and . The band running vertically down the chest gives the name and titles of Iouiya  and his speech to Nut, which is repeated also on the sarcophagus and coffins. The four straps on either side of this band name the gods of the West: On the right, Hapÿ, Anubis "Within the Temple," Kebhsenuf, and , while on the left are named Mestha, Anubis Within Ut, Duamutef, and Geb.


CANOPIC JAR-BOX OF IOUIYA.

CANOPIC jar-box in wood mounted on a sledge and covered with pitch and decorated with figures and hieroglyphic legends in stucco-gilt. The box is square, with a projecting curved cornice around the top; the lid is of the usual Egyptian box shape  and is decorated down the centre with two bands of inscriptions in stucco-gilt on a black ground. These inscriptions give the speech of the , "Favoured of his Lord Amen, Iouiya" to his mother Nut that she may spread her protecting wings over him. On the top is a gilt knob bearing the name of Iouiya.

The front of the box is ornamented with standing figures of Isis and Nephthys in stucco-gilt on a black ground, with a dado below representing a panelled wall in gold, blue, red, and green. Along the top is a horizontal band of stucco-gilt with hieroglyphs in low relief, and at the sides are vertical bands with inscriptions. The line at the top gives the speech of Geb:—



while at the sides are speeches of Isis and Nephthys:—



At the top in the centre is a gilt knob inscribed with the name of Iouiya.

At the right side of the box are standing figures of Duanutef and Mestha in stucco-gilt with the same dado as on the front. Along the top is a horizontal band of stucco-gilt with an inscription reading:—



On the two sides are vertical lines giving the speeches of Amen and Ra :—

- (1) 
- (2) 

The left side of the box is decorated with standing figures of Hapÿ and Khebsenuf facing one another in low relief in stucco-gilt with the same dado below as on the front. Along the top is a horizontal band of hieroglyphs reading :—



while at the sides are the speeches of Set-amentet and Anubis :—

- (1) 
- (2) 

On the end of the box are standing figures of Neith and Selk in low relief in stucco-gilt, with hieroglyphic legends in bands above and on either side of them. These inscriptions read :—

- (1) 
- (2) 
- (3) 

BOOK OF THE DEAD.

A ROLL of papyrus, measuring 19 metres 70 cm. (now cut up into thirty-four sheets), containing forty chapters of the Book of the Dead, purporting to have been copied from an ancient document,¹ for Iouiya. The beginning of the roll is badly worm-eaten, but the last thirty-two sheets are perfect. The writing is in linear hieroglyphs, finely written in black ink with rubrics in red ink: the vignettes illustrating the various chapters are beautifully executed in colour, and form splendid specimens of Egyptian illuminating art. The following is a list of the vignettes and chapters found in the document.

Sheet I. Iouiya and Tuiyou adore and present offerings to Osiris. Iouiya is represented standing with arms upraised in the attitude of adoration, and wearing a transparent vest, loin cloth and long shirt. On his head is a white wig; on his chin a short false beard. Around his neck is a broad necklace composed of different coloured beads with an *ab* or "heart" amulet as pendant. On his arms are gold amulets and on his wrists gold bracelets with coloured inlay. Behind him stands Tuiyou, clad in a long white crinkled and transparent garment, wide below but fitting closely round the waist. On her head is a long black wig, and large circular gold earrings are in her ears. Around her neck is a broad necklace, and she wears amulets and bracelets. In her right hand she holds a sistrum, and in her left a large garland composed of papyrus and lotus flowers and persea fruits. Before Iouiya is a mat with offerings of joints, ducks, bread, grapes, and vegetables spread upon it; and at the side of the mat three sealed-up wine jars

¹ On sheet No. 34 the papyrus ends with a note running:—



with lotus flowers twined around them. Above the offerings is a mutilated inscription in four vertical lines, explanatory of the scene :—



“(1) Giving adoration to Osiris, kissing the ground before (2) Unnefer, said
 “by the Divine Father (3) of the Lord of the Two lands, the favoured
 “of the Good God Iou (4)iya, justified.”

In front of the offerings and figures is Osiris seated upon a throne and dais. The god wears the white crown with feathers on either side and a long false beard. Around his neck is a broad necklace composed of bands of different coloured beads. He is clad in a long close-fitting garment, wears bracelets upon his wrists, and holds the \int -sceptre and scourge. Above him are three mutilated vertical lines of hieroglyphs naming Osiris and giving his titles.

Sheets 2–5. Chapters I and XVII, with vignette of Isis and Nebhat in a canoe drawn to the town by a yoke of oxen.

Sheets 6, 7. Chapter XVIII.

“ “ “ LXXXIII, with the *bennu*-bird as vignette.
 “ “ “ LXXXIV, with the *shenti*-bird as vignette.
 “ “ “ LXXXV, with the *ba*-bird as vignette.

Sheet 8. Chapter LXXVII, with the gold hawk as vignette.



“ “ “ LXXXVI, with the *meut*-bird as vignette.
 “ “ “ LXXXII, with vignette of Ptah, holding an *uas*-
 sceptre.

Sheet 9. Chapter LXXXVII, with a snake as vignette.

“ “ “ LXXXIA, with a lotus-flower as vignette.
 “ “ “ LXIII, with a vignette of Iouiya kneeling and
 holding a cup before a tree.
 “ “ “ LXIV.


Sheets 9, 10. Chapter CXXI.

Sheets 10, 11. Chapter CXC.




- Sheet 11. Chapter CIV.
 " " " CIII.
 " " " CXVIII.
 " " " CXVII.
 " " " CXIX.
- Sheet 12. Chapter CXLVIII, with vignette of a series of green-coloured cows.
- Sheets 12, 13. Chapter CXXXVIIA ("Chapters of the four flames," incomplete).
- Sheet 13. Chapter CLV.
 " " " CLVI.
- Sheets 14, 15. Chapter CLIIIA, with vignette.
- Sheets 16, 17. Chapter LXIV.
- Sheet 18. Chapter CX, with vignettes.
- Sheet 19. Chapter ? 

- Sheets 19, 20. Chapter CXLIV, with vignettes.
- Sheets 20, 21. Chapter CXLV.
- Sheets 21, 22. Chapter CXLVI, with vignettes.
- Sheets 22, 23. Chapter XCIX, with vignettes.
- Sheets 24, 25. Chapter CXXV. Introduction.
- Sheets 26-28. Chapter CXXV. Negative Confession.
- Sheet 29. Chapter C, with vignette.
 " " " CII.
- Sheets 29, 30. Chapter CXXXVI B.
 " " " CXXXVI (II).
- Sheets 30-33. Chapter CXLIXA-o.
- Sheets 33, 34. Chapter CL, with vignette.

THE SARCOPHAGUS OF TOUIYOU.

THE mummy of Touiyou was enclosed in two separate coffins nested one within the other, and placed in a large rectangular wooden sarcophagus mounted on a sledge.

The sledge and sarcophagus are both of a coarse-grained wood covered with pitch and decorated with figures and hieroglyphic legends in stucco-gilt. In shape the sarcophagus is rectangular, with a lid in the form of a projecting curved cornice and top of the common Egyptian box shape . Like the sarcophagus of Iouiya, the joints are mortice- and tenon-pinned.

Down the lid are three vertical columns of hieroglyphs, one in the centre and two on either side, giving prayers to Nut, reading:—

- (1) In the centre : 
- (2) On the right side : 
- (3) On the left side : 

At the top end of the lid, between the vertical columns of hieroglyphs, are the sacred eyes and figures of Anubis :—



At the lower end are two inscriptions, reading :—

- (1) (2)

At the top end of the box are two vertical and one horizontal bands of hieroglyphs, and a figure of Nephthys with arms upraised, standing upon a *nub*-sign. The inscriptions read :—

- (1) (2) (3)

At the lower end of the box are two vertical and one horizontal bands of hieroglyphs, and a figure of Isis with arms upraised, standing upon a *nub*-sign. The inscriptions read :—

- (1) (2) (3)

On the right side of the box are two vertical and one horizontal bands of inscriptions, and a procession of the four gods of the West. The inscriptions read :—

- (1) (2) (3)



On the left side of the box are also two vertical and one horizontal bands of inscriptions, and a procession of the four gods of the West. The inscriptions read:—



The interior of the sarcophagus is decorated with figures and inscriptions. On one end is a figure of Isis with arms upraised, and kneeling upon a *nub*-sign, while on the other end is delineated Nephthys in a similar attitude. The texts on the sides of the box give the following chapters from the Book of the Dead, with unimportant variants:—

Chapter I.

- .. XIV.
- .. XXVI.
- .. XXVII.
- .. XXXB.
- .. LXXII.
- .. XCII.
- .. CV.

OUTER COFFIN OF TOUIYOU.

The outer coffin, consisting of lid and box, is made of wood carved and covered with stucco-gilt. It is mummiform in shape, the wig is long and the hair represented by bands of incised lines. The features of the face are very finely modelled. The eyes, eyelashes, and eyebrows are inlaid; the eyes are of white marble and obsidian, the eyelashes and eyebrows of opaque violet glass.

Suspended from the neck is a necklace, and upon the chest is a pectoral: from this pectoral the hands, which are closed, protrude, the right wrist being crossed on the left, while on the right wrist is a broad bracelet. The necklace and pectoral are composed of ten bands of conventional flowers and petals inlaid in coloured glasses, with hawk-headed "spreading-pieces" at the ends.

Upon the abdomen is a figure of the goddess Nut, kneeling on one knee and with winged arms outspread. Down the lower part of the abdomen and the whole length of the legs are two vertical columns of hieroglyphs, beginning: (1) "Speech of the Royal Mother of the Great Royal Wife, the Royal Ornament, the Favourite of the Good God, the Lady Touiyon, justified," and giving the usual prayer to Nut for her protection.


Around the sides of the lid and box are represented the so-called mummy-straps, giving the same formulæ as are found on the coffins of Louiya.

Upon the wig, at the top of the head, is a figure of the goddess Nephthys with arms upraised, kneeling on a *neb*-sign. On the soles of the feet is a figure of Isis with upraised arms, kneeling upon a *nub*-sign, with a vertical line of inscription on either side of her, reading:—


(1) (2)

Below are two *ded*-signs.

Upon the wig, at the top of the head, is the figure of the goddess Nephthys with arms upraised, and kneeling upon a *nub*-sign. On either side of her are vertical lines of hieroglyphs, reading :—



Beneath the feet is a figure of Isis with arms upraised, standing upon a *nub*-sign, with the following inscription on either side of her :—





Below are two *ded*-signs.


MASK AND MUMMY-STRAPS OF TOUIYOU.

MASK of Touiyou for fitting over the head of her mummy. This mask is made of several layers of coarse linen glued together and coated with plaster. The inside is bitumened, the exterior is gilt. The wig is long, lined, and with bands at the ends; it is secured round the top of the head by a broad fillet composed of a band of lotus petals with a lotus flower and two buds on the forehead. The face is very beautifully modelled; the eyes, eyebrows, and eyelashes, like those in the mask of Louiya, are inlaid, and of the same material. The pectoral is of stucco-gilt with inlay of coloured glasses: it consists of six rows of conventional flowers and petals and drop-shaped beads. Over the front of the mask appears to have been fastened (? by gum-arabic) a black veil of very fine texture, which has been broken away in places.

Fixed over the wrappings of Touiyou were mummy-straps firmly secured by string behind. They are cut out of a piece of linen which forms the framework, and this is covered with stucco and gilt.


At the top is a figure of Nut with wings outspread, and on either side of her are the amulets  and . The band running vertically down the chest gives the name and titles of Touiyou, with the speech to Nut, which is repeated also on the sarcophagus and coffins. On either side of this central band are four straps with inscriptions naming the gods of the West, and between them are figures of those deities as well as of Isis and Nephthys. Outside these, again, are two bands of inscriptions giving the same speeches of Nut which are found on the sarcophagus.

CANOPIC JAR-BOX OF TOUIYOU.

CANOPIC jar-box in wood, mounted on a sledge, and coated with pitch and decorated with figures and hieroglyphic legends in stucco-gilt. The box is square, with a projecting curved cornice around the top; the lid is of the usual Egyptian box shape  and is decorated with bands of inscription in stucco-gilt on a black ground.

The front of the box is decorated with standing figures of Isis and Nephthys in low relief, in stucco-gilt, with bands of inscriptions at the top and sides, and a panelled dado in stucco-gilt below. The inscriptions at the sides give the speeches of Isis and Nephthys, and at the top the name and titles of Touiyou.

- (1) 
- (2) 
- (3) 

At the top, in the centre, is a gilt knob with the title  and name of Touiyou.

On the right side of the box are standing figures of Mestha and Hapÿ facing one another. The inscriptions at the sides give their speeches, and in the line above is the speech of Amentet :—

- (1) 
- (2) 
- (3) 

On the left side of the box are standing figures of Duamutef and Khebsenuf in stucco-gilt, facing one another, with bands of inscriptions giving the name and title of Touiyou, above and at the sides the speeches of Duamutef and Khebsenuf:—

- (1) 
- (2) 
- (3) 

On the end of the box are standing figures of Neith and Selk facing one another, with bands of inscriptions giving the speeches of Set-amentet, Neith, and Selk:—

- (1) 
- (2) 
- (3) 

Enclosed in the Canopic jar-box were the four canopic jars containing the viscere of the dead, each one being under the protection of a goddess and the four genii of the West. These vases are of an aragonite, finely carved, and each with lids in the shape of human heads. The viscere are carefully wrapped up in linen bands, and pressed so as to take the shape of a mummy, and each one is surmounted by a small human-headed mask in canvas stucco-gilt.

The vase containing the stomach was under the protection of Mestha, and bears four vertical lines of incised hieroglyphs, reading:—














- (1) 
- (2) 
- (3) 
- (4) 



FUNERARY STATUETTES OF IOUIYA AND TOUIYOU.

EIGHTEEN funerary statuettes in the form of a mummy (fourteen bearing the name of Iouiya and four the name of Touiyou) were found: they are all of exceptionally fine modelling and carving. Of those bearing the name of Touiyou, two are of wood plated with gold, and two of wood plated with silver, having gold-plated faces, hands and pectorals. Of those inscribed with the name of Iouiya, two are of ebony, one is of pine, eight are of cedar, and two are of a commoner wood painted to imitate cedar. The specimen figured is of carved wood, with the face and body covered with two plates of beaten copper pinned down on either side. The wig is cut in the wood, is short, and painted black. The features are exquisitely modelled, and the eyes are painted with white pupils and black irises. The pectoral is formed of a band of stucco-gilt, and from the neck is suspended an *ab* or heart amulet. In the right hand is a ⤵ -baton, and in the left the ⤵ -thong. None of the figures are represented, as is usual with funerary statuettes, with the pick, hoe, and basket; but a set of models of these implements was found alongside the figures. These models comprise three pairs of copper baskets, twelve yokes of wood, twelve hoes, twelve picks, and a brick-mould. This latter is of considerable interest, and was very rarely laid with the other implements.¹

The inscription engraved upon these funerary statuettes is the usual *Shawabti* text, which forms the Sixth Chapter of the Book of the Dead, with some unimportant variants in the spelling of words. The text gives instructions whereby the statuette may be made to do the work for a person

¹ A text on a funerary statuette of the Seventeenth Dynasty found at Draḥ abu'l Negga runs: "If thou art called to do any work in the Underworld of a person according to his duties (either) to carry water, to make bricks, to carry sand from west to east, &c."

in the Netherworld. The name of Iouiya is spelt variously on the different figures: , , , or , and the titles given are (1) , , or more fully  "Divine Father" and "Divine Father of the Lord of the Two Lands," and  "Favourite of the King," and  "Favourite of the Good God." The name of Touiyon is spelt on her four figures , and the titles given are  "Favoured of the Good God (*i.e.*, the King),"  "Royal Ornament," and  "Great one of the Harâm of Amen."

Besides the eighteen funerary statuettes, thirteen wooden boxes for the figures were discovered. These boxes are rectangular, upright-oblong in shape, with curved lid, and are painted on the outside with upright panels of red, blue, and green, divided by narrow white lines; on the insides they are coloured with yellow paint. Four only of the boxes are inscribed. One of them bears a vertical inscription down the front giving the *De hetep seten*, "May-the-King-give-an-offering" formula "to Osiris, Within the West, that he may present all that which issues upon his altar for the *ka* of the Favoured of the Good God, Iouiya, justified;" on its lid is the inscription  "Devoted towards Osiris Yau, justified." The three other inscribed boxes bear a similar text upon the lid but the names and title of Iouiya are written  "The Divine Father, Áiai."

ALABASTER VASE BEARING THE NAMES OF AMENOPHIS III AND QUEEN THIYI.

LARGE vase in alabaster, with foot, spherical body, neck, and cover. The neck is long, curves outwards towards the top, and terminates in a narrow projecting rim. The cover or cap is hemispherical in shape, with a slightly projecting rim curving outwards and fitting the rim of the neck of the vase. The belly of the vase is spherical, and rests on a narrow circular foot.

On the neck is inscribed in incised hieroglyphs the prenomens and nomens of Amenôphis III with his titles and the name and titles of Queen Thÿï. The alabaster or aragonite from which the vase is carved is of exceptionally fine quality.

MAGICAL FIGURE OF IOUIYA.

With the funerary statuettes was found a single figure, mummiform in shape and beautifully carved in cedar-wood, bearing down its front two vertical columns of incised hieroglyphs, the first giving, in an abbreviated form, the text of the "Chapter of the Flame" from the Book of the Dead (Ch. CLI f.); the second, a shortened version of the "Chapter of the Magical Figure of the Northern Wall," from the Book of the Dead (Ch. CLI, d.). The bases of similar figures were found by Mr. Davis in the Tomb of Thoutmôsis IV (Carter and Newberry, *The Tomb of Thoutmôsis IV*, p. 9).

ALABASTER VASE.

LARGE vase in alabaster, with foot, spherical body, neck, and handle. The neck is long and terminated by a wide projecting rim; the handle is connected at the neck and bends downwards towards the belly; the foot is circular.

The alabaster is stained as with some oily substance that was no doubt contained in it. The mouth was covered with a piece of linen, which was tied by a strand of string secured by a pellet of clay and sealed.

ALABASTER VASE.

VASE in alabaster, with foot, spherical body, neck, and handle. The neck is long, cylindrical in shape, and terminates in a wide projecting rim. The handle is connected at the top of the neck below the rim, and bends downwards towards the belly, where it terminates in two papyrus flowers, delicately cut. The belly is spherical, resembling a mace-head in shape, and rests on a narrow projecting foot, a third of which has been chipped away.

The alabaster is of fine quality and very delicately carved. On the upper part of the handle are the remains of a piece of linen used for securing the vase's contents.

DUMMY VASES.

BESIDES the vases in alabaster, there were found in the tomb of Iouiya and Touiyou twenty-seven "dummy" vases in wood and terra-cotta, painted to represent alabaster, glass, black and white diorite, and red breccia.

The shapes of these dummy vases are various, ranging from the plain cylindrical vase with projecting rim, to the long-necked vase with spherical body and long handle. The number of the various forms may be grouped as follows :—



Four coloured to imitate alabaster; two representing blue glass with yellow wave lines, and two dark blue glass with band of lotus petals around the neck.





Two coloured to represent blue-green glass with yellow wave lines; two representing blue glass with yellow wave lines and rosettes; six representing alabaster, and one of pottery painted white and varnished, the varnish having turned a bright brown. Of this form there are also two wooden vases, painted to imitate alabaster with a band of lotus petals around the upper part of the belly.






Of this type of vase there are eight specimens, all of them painted to represent black and white diorite, or red and white breccia. Around the neck of one of the vases of this form is painted a band of lotus petals.

AMULETS.

AMBER SCARAB inscribed with a magical text in five horizontal lines of hieroglyphs, and bearing the name of Touiyou. On the base at the top is incised the hieroglyphic , and the text reads:—



SCARAB-AMULET in dark blue glass to imitate lapis lazuli and exquisitely modelled. It stands upon a green beryl base, to which it is cemented by a thick layer of cement. The base is inscribed with the text of the Chapter of the Heart from the Book of the Dead, in ten horizontal lines of hieroglyphs. The first line gives the name of Touiyou  "Touiyou she says," and the second begins  "He says My heart." The duplication of the word  and the alteration of the third person suffix from feminine to masculine, shows that this scarab was originally made for a man, and that the name of Touiyou was inserted afterwards.


SCARAB-AMULET in green beryl, with head chipped, and inscribed with the Chapter of the Heart from the Book of the Dead. It bears the name of Touiyou.

Ded-AMULET of wood, stuccoed and gilt, and inscribed with the name and titles of Touiyou, and the text of the 155th Chapter of the Book of the Dead:—



Ded-AMULET in blue faience, with narrow bands of gold-foil at the top, centre, and bottom.

Sa-AMULET of red jasper, inscribed with a magical text reading:—




Ba-BIRD in wood, painted and inscribed upon the base with the name of Touiyou.

SEALINGS in clay, with impressions of an oval-shaped seal representing a recumbent Anubis, with nine prisoners with arms tied behind them below.

MODEL MIRROR, with plain handle of wood, stucco-gilt, and plate made of canvas, stuccoed and coloured blue.

KOHL-TUBE in light blue-glazed faience, with a vertical line of hieroglyphs in dark violet glaze inlay, giving the names and titles of Amenôphis III:

. This Kohl-tube is fitted with an ebony needle, and stoppered with a piece of papyrus pith; it is slightly chipped at the mouth of the tube.

THE CHARIOT.

THE chariot bears no name, but we may presume that it belonged to Louiya. It is in nearly perfect preservation: the framework of the body, the wheels and the pole, are intact, and even the leather-work which has been stripped from the sides of the "body" has been found, and could be put back in place. It is doubtful whether it was ever used except for the funeral procession, for the leather tyres are hardly scratched.

The body, 90 cm. in breadth, consists of a semicircular framework half open at the back, with a floor of leather mesh-work for the charioteer to stand on. The floor is formed of a bent rod with rectangular holes, through which the leather mesh-work is lashed, while the back piece consists of a board about an inch in thickness, to the front of which, through holes, the leather mesh-work is lashed, and underneath which the butt end of the pole is fastened. The front of the body consists of a bent rod or rail above, supported by ten wooden uprights arranged at equal distances. The body is supported by the pole and by the axletree: its front is lashed to the pole which is carried under the centre of the body to the back-piece of the floor in which the butt end of the pole is fastened. The back is supported by the axletree, to which it is bound at the ends and at four equal intervals between. The axletree is made out of a solid beam about two-and-a-half inches thick.

The wheels are 75 cm. in diameter and are six-spoked; the spokes are morticed and tenoned into a nave, 7 cm. in diameter, formed by a hollow wooden cylinder, through which the axletree runs. The wheels are kept in place by lynch pins outside and by the thickness of the axletree on the inside. The rim of the wheel is formed of two pieces of bent wood lashed together, the lashings being covered by stucco-gilt. The tyre of the wheel is made of strips of leather sewn together and stained red, with leather padding below.

The pole is about 2 metres long, and 6 cm. from the end is a hole, to which the yoke was pinned by a wooden peg and lashed. The yoke is made of a single piece of bent wood, with round knobs at the ends and four bands of stucco-gilt at equal intervals around it. The pole is bent into an elbow, where it meets the body and then flattens out to a breadth of 5 cm. It is dovetailed into the back-piece of the body, whilst in front it is lashed to the frame of the body, the lashings being covered with stucco-gilt.

The front, sides, and back of the body were filled in, above, by two sheets of red leather with green and white appliqué border, fixed by copper pins, and below, by leather stuccoed and gilt with decoration in low relief in imitation of embossed leather-work. This decoration consisted, in the centre, of two goats browsing upon a conventional "tree of life," with a row of rosettes running along the sides and bands of coil patterns on either side, and panels at the ends with "trees of life" made out of conventionalised lotus flowers. At the back, on the left-hand side, the upper part is filled in with plain red leather with appliqué border, and below is a panel of rosettes framed by a coil-pattern border with a conventional "tree of life" on the left-hand side.




H.C.



H.C.

GILT STUCCO PANELS FROM BED.



H.C.

DETAIL OF CARVED CHAIR BACK.

CHAIR OF PRINCESS SAT-AMEN.

THE largest and most elaborate of the three chairs bears the name of Sat-amen, daughter of Amenôphis III by Queen Tiyi, and consequently a granddaughter of Iouiya and Touiyon.

The chair is made of wood, the various parts being fixed together by mortice and tenon joints, pegged. It is 77 cm. high; the seat is 34 cm. from the ground, 52 cm. wide, and 54 cm. deep. The back and frame of the seat are constructed of a common wood veneered with a rarer one, probably walnut; the veneer is about one-eighth of an inch thick, and is pinned down with small wooden pins. The legs are carved out of solid blocks of walnut. The back is high, curved to fit the body, slopes outwards towards the top and is supported at the back by three uprights rising vertically from the back of the frame of the seat. The arms are built of a frame of solid wood containing a panel, the upper pieces of the frame curving upwards to the back of the chair. Upon the top of the frame is a moulding of wood gilt, projecting slightly over the thickness of the arm; it is pegged to it and carried in a curve to the top of the back, and ends in front in finely carved gilded busts, which are pegged on to the frame of the seat. The seat is composed of plaited string threaded through holes in the framework and tied beneath. It is supported on four legs, carved to represent the fore and hind legs of a lion, the feet of which rest on small ∇ -shaped bases covered with silver-foil. Between the two front legs and the two back legs are cross-bars rounded, and terminating with bands of gold at the ends, while attached to the frame immediately beneath the seat is a curved support to give extra strength to the seat.

The decoration (see fig. 1) is modelled in gesso and gilt. On the back it consists of a winged disc with uraei and the name "Edfu" on either side. Below this is a rectangular panel containing a scene in duplicate \longleftrightarrow , showing Sat-amen seated receiving an offering of a gold necklace from a female slave or attendant. The inscription above the Princess reads: "The eldest daughter of the king whom he loves, Sat-amen," while that above the slave explains the scene "offering gold of the lands of the South." The whole is framed at the top and on either side by a band of rectangles with a frieze of hanging lotus flowers and buds.




FIG. 1. DECORATION ON BACK OF THE CHAIR OF PRINCESS SAT-AMEN.

The Princess is clad in a close-fitting vest and a long crimped skirt reaching to the ankles. She wears a short wig, secured round the top of the head by a narrow fillet tied behind in a bow: over the forehead is a small gazelle head with horns. Upon the top of the head is a crown, consisting of a disc, from which issue three lotus flowers with buds between. From this crown hang flaps, one on either side of the head, reaching to the breasts. In her ears are earrings, and around her neck is a broad necklace, consisting of three bands of lotus petals. On the wrists are bracelets, and in her right hand she holds a sistrum and in her left a *menat*. The chair that she is

seated on has a high back, and its arms are shown covered with a scale pattern; its legs are modelled after the fashion of those of the lion. The chair is placed on a large mat, and a small one is represented beneath the Princess's feet.

The slave or attendant is clad in a close-fitting vest and long skirt ornamented by horizontal decorated bands. She wears a short wig, secured by a fillet over the forehead with bow tied behind, and on the top of it is a disc. In her ears are earrings; around her neck is a broad necklace and on her wrists are bracelets. She holds before her in her two hands a mat with broad gold necklace or pectoral upon it.




FIG. 2. LEFT-HAND PANEL OF ARM OF CHAIR OF SAT-AMEN.

The scene is continued in the panels on the insides of the arms, where four female slaves are depicted bearing offerings of gold rings. These females are clad in elaborately ornamented embroidered or tapestry-woven garments, and wear discs on their heads consisting of three lotus flowers or of three rosettes.

On the outside panels of the arms are also scenes in gesso gilt. On the one (fig. 2) is a figure of Tauris standing between two dancing figures of Bes. The first figure shows the god of music clad in a short skirt dancing to the strains of a tambourine, which he is beating with his right hand. The second figure depicts him armed with two knives and dancing a jig. On the other are three figures of Bes dancing (see fig. 3).

These scenes of Bes and Thueris (the latter, it should be remarked, is *lion*,¹ not hippopotamus-headed) are interesting. Bes dancing to the notes of his tambourine is a motive already known to us from some small faïence figures and ring bezels found in the ruins of the Palace of Amenôphis III at Thebes, and in the town of Akhenaten at Tell el Amarna. The attitude and liveliness of these figures is unlike anything else that we know of Upper Egyptian art, and suggests a Delta or perhaps a foreign origin. But, unfortunately, we know as yet too little about the civilisation of the Eastern Mediterranean at this date (B.C. 1400) to allow of anything definite being said on the subject. Already in the time of Thoutmôsis III several new motives are found in Egyptian art, due no doubt to the trade relations that




FIG. 3. RIGHT-HAND PANEL OF ARM OF CHAIR OF SAT-AMEN.

had sprung up between the peoples of Western Asia and Egypt. At a slightly later period foreign artisans were brought to the Nile Valley and introduced the arts of glass-making and tapestry-weaving, and the

¹ The lion-headed Thueris is otherwise unknown in Egyptian art. Professor Bosanquet has kindly supplied me with the following notes on the subject:—

“The appearance of a lion-headed goddess on a piece of furniture made in Egypt in the reign of Amenôphis III supplies a fresh confirmation of the view that the lion-headed demons of Mycenaean art were ultimately derived from Egypt. Dr. Winter connected them with the Egyptian hippopotamus-goddess, Thueris.¹ Dr. Arthur Evans has proposed a different name, that of Ririt, the female hippopotamus, which in Egyptian art stands for the constellation known to us as ‘Charles’ Wain.’² The design on the chair of Princess Sat-amen shows the transition from the hippopotamus-head to the lion-head, already

¹ *Jahrbuch des k. d. Archäol. Instituts*, V (1890), p. 108 (Anzeiger).

² *Journal of Hellenic Studies*, XXI (1891), p. 169.

extraordinary proficiency which they displayed shows that their skill must have been the result of generations of work and experience. To what civilisation these foreign workmen belonged we do not as yet know for certain, and it is perhaps fruitless to conjecture until explorations have been made on sites in the Delta and in other countries bordering on the Mediterranean.

accomplished on Egyptian soil. The Mycenaean figures which Winter explained as blundering imitations of the Thueris type are as follows:—

- (A) A pair of demons holding ewers, repeated three times on each handle of a bronze vessel found in Cyprus and preserved in the New York Museum.³ Of all the Mycenaean examples these come nearest to the Egyptian figure on the chair; they wear on shoulders and back a continuation of the lion's mane, forming a back-covering somewhat broader and longer than that of the Egyptian figure, but otherwise, as Mr. Myres was the first to remark, 'exceedingly like it.' There is no sign of feminine breasts.
- (B) Three figures with apparently asinine heads, bearing on their shoulders a pole, painted on a fragment of wall-plaster found at Mycenae.⁴ Their tongues loll out, and give the same effect in profile as the tuft of hair under the chins of the lion-headed demons on the bronze vase. They wear the same slaggy back-covering, but in this case it is confined about the waist by a belt, and was certainly understood by the painter as a detachable garment.
- (C) A series of glass plaques found by Tsountas at Mycenae, representing pairs of lion-headed figures holding ewers. Between them rises in most cases a cairn or a pillar, over which they seem about to pour a libation.⁵ The back-covering is always belted.
- (D) Zoocephalous demons, single or in pairs, on engraved gems. On a gem found at Vaphio they stand face to face holding ewers, about to water a palm-tree growing in a pot at their feet: in two cases a single ewer-bearer is represented.⁶ On a lentoid gem from Mycenae a similar demon, without the ewer, stands between two supporting lions.⁷ On another lentoid the ewer-bearing demons act as supporters at either side of a human figure.⁸ Other stones show the demon carrying slaughtered animals on a pole, or lifting on his shoulders a dead bull.⁹ In most cases the belt as well as the hairy back-covering is distinctly represented. The latest addition to the series is a much-worn cylinder from Palaikastro in Crete, on which the lion-headed demon is associated with two female figures and two trees.¹⁰

The adoption of this Egyptian type and its diffusion through the Minoan world was no doubt due to the fact that it gave concrete expression to a belief in composite monsters which was already current there.

³ Perrot and Chipiez, *Art in Phœnicia and Cyprus*, II, pp. 363, 364. *Journal of Hellenic Studies*, XIV (1894), p. 104.

⁴ *Ephemeris Archaeologike* (1887), Pl. X. Compare *Journal of Hellenic Studies*, XIV, pp. 81 and 101, where Mr. A. B. Cook argues that the object which they carry is a rope, not a pole, because it is covered with diagonal markings; but comparison with other Mycenaean paintings does not confirm this view. The diagonal lines were added to distinguish the pole from the background.

⁵ Published by Dr. A. J. Evans, *Journal of Hellenic Studies*, XXI, p. 117.

⁶ *Journal of Hellenic Studies*, XIV (1894), p. 84, fig. 4; and p. 106, figs. 6, 7, 8.

⁷ *Journal of Hellenic Studies*, XXI (1901), p. 168.

⁸ *Journal of Hellenic Studies*, XIV, p. 120, fig. 14.

⁹ *Journal of Hellenic Studies*, XIV, p. 84, figs. 2 and 3.

¹⁰ *Annual of British School at Athens*, VIII (1902), p. 302.

CHAIR BEARING THE NAMES OF QUEEN TIYI AND PRINCESS SAT-AMEN.

This chair bears a scene upon the back showing Queen Tiyi and two princesses—one of whom is Sat-amen—in a papyrus canoe. Its dimensions prove that it must have been made for a child, and as the gold has been rubbed off and patched again in places, it is probable that it was used by the Princess Sat-amen when a child. The seat was originally of plaited string, which had no doubt been worn through and then cut out and a rectangular board, painted yellow, inserted.

The chair is made of a coarse-grained wood, the various parts being fixed together by mortice and tenon joints, pegged. With the exception of the seat, which is painted yellow, the whole chair is covered with stucco and gilt. The back is high, curved to fit the body, slopes outwards towards the top, and is supported at the back by the uprights rising vertically from the back of the frame of the seat. The arms are built of a frame of solid wood, the upper pieces of which curve upwards to the back of the chair. Upon the top of the frame is a moulding of wood gilt, projecting slightly over the thickness of the arm and carried down to the outside corner of the frame of the seat. Within the frame of the arms are figures of Thueris and Bes carved in the round and fixed by mortice and tenon joints above and below.

The rear is composed of a woodwork frame containing a rectangular board, painted yellow. The frame has been pierced at short intervals by small holes through which, no doubt, string was threaded to form a plaited string seat. It is supported on four legs, carved to represent the fore and hind legs of a lion, the feet of which rest on small ∇ -shaped bases. Between the front pair of legs and the back pair, and attached to the frame imme-

diately beneath the seat, is a curved support to give extra strength to the seat. The height of the back is 61 cm., of the seat 235 mm., and the depth of the seat is 35 cm.

The decoration of the chair is modelled in stucco-gilt. On the outer face of the back (see fig. 4) it consists of a scene representing Queen Tiyi and two princesses on a papyrus boat in a marsh, the whole being framed by a row of *khekar* ornaments above and a delicate coil pattern on either side. The queen is shown seated in a high-backed chair with arms. She



FIG. 4. DECORATION ON BACK OF THE CHAIR BEARING NAMES OF QUEEN TIYI AND SAT-AMEN.

is clad in a close fitting vest with long, thin and transparent crimped skirt. On her head she wears a double feathered crown and long wig. Around her neck is a broad necklace, while on her arms are amulets. In her right hand she holds an *ankh* and in her left a flail or fly-flip. Beneath her seat is seated a cat with tail erect. Above her is her name, "The Great Royal Wife Tiyi." In front of the Queen and in the prow of the canoe stands the young princess Sat-amen offering her mother a bunch of lotus flowers which

she holds before her in her right hand. She is clad only in a short skirt with long girdle tie. She wears her hair short behind with long curls hanging down either side of the face. On her head is a diadem or tiara, consisting of five upright lotus flowers with long stalks, with a lotus bud hanging down over the forehead. Around her neck is a bead necklace and on her arms are amulets. In her left hand is a feather fan with long handle. Behind the Queen stands, in the stern of the canoe, a second princess, who holds before her a large fan with a garland of lotus and poppy flowers arranged up its handle. The canoe is made of papyrus stalks with papyrus and lotus flowers at prow and stern. Below it is a double row of papyrus reeds.

On the back of the chair, on a rectangular panel, is a figure of Bes with wings spread out from his sides and knives fixed to his feet. On either side of him he holds a *neb*-basket in which are *ankh* and *sa*-amulets. This figure is partly hidden by the centre wooden upright supporting the back of the chair.

OSIRIS BEDS.




In one section of the chamber of the tomb were found two "beds of Osiris," one each for the persons buried. The beds consist of a rectangular frame of wood divided by two longitudinal and six transverse bars pinned together with wooden pegs. Upon the top of the frame has been fixed a papyrus-reed mat, and over the whole a double sheet of linen has been stretched and sewn together at the ends and below in order to keep it taut. Upon the top of this, in the middle, an outline of the figure of Osiris facing to the left has been traced in ink. The surface thus outlined was sprinkled with earth and sand and afterwards sown with grains of barley. This small plantation was carefully watered till the grains germinated and grew, and then, when the young corn had reached the height of about eight inches, it was pressed flat by the whole bed being wrapped in a sheet of linen and allowed to dry before it was deposited in the tomb.

The only other example of an Osiride figure made of growing corn was that found by M. Loret in the tomb of Maa-her-pa, and has been described by M. Daressy in his *Catalogue*¹ of the objects found in that tomb. The signification of these "beds" is, according to Professor Wiedemann,² the material expression of the idea of life springing from death, as the new corn springs from the old seed laid in the ground. Osiris had vegetated in this way before his resurrection, as is seen by the pictures on the walls of the temples of the Græco-Roman period.


¹ *Catalogue Général des Antiquités Égyptiennes du Musée du Caire*, No. 24,661.

² Wiedemann, in an article on "Osiris végétant" in the *Museon*, nouvelle série IV, 1903 pp. 111-123. Margaret Murray, *The Osireion*, pp. 28-29.

COFFER BEARING THE NAMES OF AMENOPHIS III.

COFFER raised on four legs, consisting of a cavetto cornice and a frieze of blue glazed faïence tiles, enriched with hieroglyphic signs , symbolising "Life, Stability and Power," formed in gilt gesso in low relief. The top is in two folding leaves, hinged at either side and opening in the centre, and decorated with a painted design of two -figures kneeling upon a -sign and bearing upon their heads the cartouches of Amenôphis III.



The angle-posts of the collar are carried down to form the legs, which spread slightly towards the feet. Immediately below the frieze the whole construction is strengthened by a system of cross-bracing, in the form of king and queen post trusses. This form of construction combines the maximum of strength with the minimum amount of material.

Upon the lids are fixed wooden knobs, inscribed with the names of Amenôphis III, and on either side of these knobs are wooden -bolts running in copper-wire hoops.


Height, 51 cm. Length, 53 cm. Breadth, 42 cm.

COFFER BEARING THE NAMES OF AMENOPHIS III AND QUEEN THYI.

COFFER raised on four legs, consisting of a cavetto cornice and a frieze of blue glazed tiles, enriched with hieroglyphic inscriptions formed in gilt gesso in low relief. A curved segmental lid rests on the top of the cornice. The angle-posts of the coffer are continued downwards and form parallel legs with a cross rail below the frieze.


Around the ends and sides of the lid is a border of rectangles, encrusted with pieces of ebony, ivory, stained red ivory and blue glazed faïence. Within this border are two panels of blue glazed faïence divided across the middle and decorated with designs in gilt gesso, in the lower half with -figures kneeling upon a -sign, and in the upper half with the cartouches of Amenôphis III, surmounted by double feathers and the sun's disc with uræi.


The cavetto cornice is in stucco-gilt, and the frieze consists of a panel of blue glazed faïence tiles, with, on either side of the coffer, the titles and names of Amenôphis III, and on the ends the titles and names of Queen Thÿi, the whole being bordered above and below by a band of encrusted coloured rectangles, similar to those on the lid.

The space between the frieze and the cross rail below it is filled in with pierced ornament, consisting of a series of  carved in wood and gilt, and backed by stained red linen of very fine texture. The angle-posts and rails are encrusted on the outer faces with bands of coloured rectangles.

On the lid and on one end of the coffer are wooden knobs, around which the string to secure the lid was fastened.

STAFF AND WHIP.

WOODEN STAFF covered with stucco and painted black to represent ebony, and ornamented at the upper end with seven double bands of gold, representing string binding; between the gold bands the staff is coloured alternately red and black, and in each division are five flowers with gold centres and yellow dots around to represent petals. On the top end of the stick is incised a rosette in gold. Down the staff is an inscription in yellow hieroglyphs, reading:  "The veteran in the service of Osiris, the favoured one of the Good God Iouiya, justified." The staff is broken at the lower end and measures 115 cm.

WHIP-HANDLE of wood with leather thong. The handle is painted black to imitate ebony, and at the upper end is ornamented with four lines of white to imitate ivory. Down the handle is an inscription, reading:  "The veteran in the service of Osiris, Iouiya." The handle measures 396 cm. in length.



SARCOPHAGUS OF IOUYIA




OUTER COFFIN OF IQUJIYA.



SECOND COFFIN OF IOUIYA.




WINE-COFFIN OF TOMBA




CANOPIC-JAR BOX OF IOUIYA.

100-100
100-100
100-100
100-100



PAGE FROM PAPYRUS BOOK OF THE DEAD OF IOIYA



SARCOPHAGUS OF TOUIYOU.



OUTER COFFIN OF TOUIYOU.




INNER COFFIN OF TOUIYEB.

NEW YORK UNIVERSITY
LIBRARY
100 UNIVERSITY PLACE
NEW YORK



CARTONNAGE MASK OF TOUIYOU.



CANOPIC JAR BOX OF TOUIYOU.



CANOPIC JAR WITH MUMMIFIED LIVER.
SURMOUNTED BY CARTONNAGE MASK




GOLD- AND SILVER-PLATED SHAWABTI FIGURES OF TOUIYOU.



WOODEN SHAWABTI FIGURE OF IOUIYA.



WOODEN SHAWABTI FIGURE OF IOUIYA WITH BOX.




MODEL IMPLEMENTS OF SHAWABTI FIGURES.

UNIVERSITY
LIBRARY
JULY 1954



MAGICAL FIGURE OF IOUIYA



MODEL COFFIN
LENGTH 30 CM.




RECUMBENT FIGURE.
LENGTH 30 CM.



ALABASTER VASE OF AMENHOTEP III AND

1894-1895

1894-1895





ALABASTER VASE

HEIGHT 345 MM.



ALABASTER VASE

HEIGHT 20 CM.



PAINTED DUMMY VASES OF WOOD

NEW YORK UNIVERSITY
LIBRARY
LIBRARY



PAINTED DUMMY VASES OF WOOD.


NEW YORK UNIVERSITY
LIBRARY •
LIBRARY •




PAINTED STONE VASES ON WOODEN STANDS.



MUMMIFIED JOINTS IN WOODEN CASES.



MUMMIFIED BIRDS IN WOODEN CASES



BACK VIEW OF CHARIOT

NEW YORK UNIVERSITY
LIBRARY OF THE
GRADUATE SCHOOL
• 100 •



CHAIR OF SAT-AMEN.

THE NEW YORK PUBLIC LIBRARY
ASTOR LENOX TILDEN FOUNDATION
1009 BROADWAY
NEW YORK



BACK VIEW OF CHAIR OF SAT-AMEN.

REV. Y. ...
...
...



CHAIR WITH CUSHION.

NEW YORK UNIVERSITY
LIBRARY



CHAIR OF TIYI & SAT-AMEN.




BED WITH PANELLED HEAD-PIECE.




COFFER BEARING THE NAMES OF AMENOTHESES III.



COFFIN BEARING THE NAMES OF AMENOTHES III. AND QUEEN TIYE



PAINTED WOODEN BOX OF AMENOTHE'S III
LENGTH 38 CM. HEIGHT 15 CM.



WIG-BASKET

LENGTH 107 CMS. HEIGHT OF CM



OBJECTS FROM THE TOMB OF IOUIYA.



PAPYRUS & LEATHER SANDALS.



JJLY 70

N. MANCHESTER,
INDIANA

